

PROJECT NO. & DESCRIPTION: T-601005.13 - Alley from 17th Street to 16th Street between Buchanan St. and Clay St.

Bid Date: THURSDAY, JULY 30, 2009

NO.	DESCRIPTION	Ewg	QTY	UNIT	Wildcat		Graybeal		Meadows		Singer Exc.	
					PRICE	TOTAL	PRICE	TOTAL	PRICE	TOTAL	PRICE	TOTAL
1	Pavement Removal		1250	S.Y.								
2	Unclassified Excavation		10	C.Y.								
3	Supplemental Borrow		20	C.Y.								
4	Subgrade Preparation		1,187	S.Y.								
5	7" Reinforced Concrete Pavement		950	S.Y.								
6	8" Non-Rein. Concrete Pavement		32	S.Y.								
7	6" Concrete Approach Pavement		467	S.F.								
8	6" Asphaltic Concrete Pavement		2	S.Y.								
9	Combined Concrete Curb & Gutter, Type I		34	L.F.								
10	Combined Concrete Curb & Gutter, Type II		28	L.F.								
11	Crushed Rock Surfacing (AB-3)		8	TON								
12	4' Dia. Standard Manhole, Type 1		2	EA.								
13	Additional Depth of 4' Dia. Standard Manhole, Type 1		18.2	V.F.								
14	10" Sanitary Sewer Pipe, In Place		227	L.F.								
15	4" Service Wye		16	EA.								
16	4" Schedule 40 PVC		150	L.F.								
17	4" Connector		16	EA.								
18	Trench & Backfill, Type 'A', 14'-16' Depth		227	L.F.								
19	Seed & Fertilize		0.1	Ac.								
20	Traffic Control		1	L.S.								
21	Project Sign, Type A		1	EA.								
TOTAL BID						185195.31		129758.65		107468.50		127451.00

PROJECT NO. & DESCRIPTION: T-601005.13 - Alley from 17th Street to 16th Street between Buchanan St. and Clay St.

Bid Date: THURSDAY, JULY 30, 2009

NO.	DESCRIPTION	QTY	UNIT	Herrmans Exc		Fastrac		PRICE	TOTAL	PRICE	TOTAL
				PRICE	TOTAL	PRICE	TOTAL				
1	Pavement Removal	1250	S.Y.								
2	Unclassified Excavation	10	C.Y.								
3	Supplemental Borrow	20	C.Y.								
4	Subgrade Preparation	1,187	S.Y.								
5	7" Reinforced Concrete Pavement	950	S.Y.								
6	8" Non-Rein. Concrete Pavement	32	S.Y.								
7	6" Concrete Approach Pavement	467	S.F.								
8	6" Asphaltic Concrete Pavement	2	S.Y.								
9	Combined Concrete Curb & Gutter, Type I	34	L.F.								
10	Combined Concrete Curb & Gutter, Type II	28	L.F.								
11	Crushed Rock Surfacing (AB-3)	8	TON								
12	4' Dia. Standard Manhole, Type 1	2	EA.								
13	Additional Depth of 4' Dia. Standard Manhole, Type 1	18.2	V.F.								
14	10" Sanitary Sewer Pipe, In Place	227	L.F.								
15	4" Service Wye	16	EA.								
16	4" Schedule 40 PVC	150	L.F.								
17	4" Connector	16	EA.								
18	Trench & Backfill, Type 'A', 14'-16' Depth	227	L.F.								
19	Seed & Fertilize	0.1	Ac.								
20	Traffic Control	1	L.S.								
21	Project Sign, Type A	1	EA.								
	TOTAL BID				121906.55		103652.09				